

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT			1. CONTRACT ID CODE J		PAGE OF PAGES 1 4	
2. AMENDMENT/MODIFICATION NO. 0001		3. EFFECTIVE DATE 27-Feb-2006		4. REQUISITION/PURCHASE REQ. NO. DPWOMA6045N119		5. PROJECT NO.(If applicable)
6. ISSUED BY FORT BRAGG DIRECTORATE OF CONTRACTING ATTN: SFCA-SR-BR BUILDING 3-1632 BUTNER ROAD FORT BRAGG NC 28310-5000		CODE W91247		7. ADMINISTERED BY (If other than item 6) ANNA WALKER ANNA.WALKER@US.ARMY.MIL PH: (910) 432-8262 FAX (910) 396-2674 FORT BRAGG NC 28310		CODE W91247
8. NAME AND ADDRESS OF CONTRACTOR (No., Street, County, State and Zip Code)				<input checked="" type="checkbox"/> 9A. AMENDMENT OF SOLICITATION NO. W91247-06-T-0059		
				<input checked="" type="checkbox"/> 9B. DATED (SEE ITEM 11) 24-Feb-2006		
				10A. MOD. OF CONTRACT/ORDER NO.		
				10B. DATED (SEE ITEM 13)		
CODE		FACILITY CODE				
11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS						
<input checked="" type="checkbox"/> The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offer <input type="checkbox"/> is extended, <input checked="" type="checkbox"/> is not extended. <p>Offer must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended by one of the following methods: (a) By completing Items 8 and 15, and returning _____ copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.</p>						
12. ACCOUNTING AND APPROPRIATION DATA (If required)						
13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS. IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.						
A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.						
B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(B).						
C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:						
D. OTHER (Specify type of modification and authority)						
E. IMPORTANT: Contractor <input type="checkbox"/> is not, <input type="checkbox"/> is required to sign this document and return _____ copies to the issuing office.						
14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.)						
a. The purpose of this amendment is to make the following changes: (1) change Block 7 Code from DABK07 to W91247 (2) Add the following statement in Section C "The estimated price for this project is less than \$25,000". b. All other items remain the same.						
Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.						
15A. NAME AND TITLE OF SIGNER (Type or print)				16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print)		
				TEL: _____ EMAIL: _____		
15B. CONTRACTOR/OFFEROR		15C. DATE SIGNED		16B. UNITED STATES OF AMERICA		16C. DATE SIGNED
_____ (Signature of person authorized to sign)				BY _____ (Signature of Contracting Officer)		27-Feb-2006

SECTION SF 30 BLOCK 14 CONTINUATION PAGE

SUMMARY OF CHANGES

SECTION C - DESCRIPTIONS AND SPECIFICATIONS

The following have been modified:

SCOPE OF WORK

Point of Contact for this project: Anna M. Walker, (910) 432-8262

This requirement is set aside for emerging small business concerns only. Emerging small business means a small business concern whose size is no greater than 50% of the numerical size standard applicable to the NAICS Code assigned to this acquisition.

The North American Industry Classification (NAICS) Code for this acquisition is 238210.

The Small Business Size Standard is for the firm to that has earned no more than \$12,000,000.00 during the preceding three (3) fiscal years.

Provide the contractor's DUNS Number and Federal Tax ID with quotation_____.

SITE VISIT:

DATE AND TIME: 1 March 2006 @ 1000 AM

LOCATION: DPW CONTRACTING OFFICE ON THE CORNER OF REILLY AND BUTNER ROAD, BUILDING 3-1632 (FRONT PORCH)

The estimate for this project is less than \$25,000.

GENERAL AND SPECIAL PROVISION

PROJECT: F9-00012-6P

1. GENERAL: The contractor shall furnish all labor, materials, equipment, tools, supervision, transportation, and any other items necessary to **install electrical connenction**. All work will be in strict compliance with these specifications, construction standards, building codes, and other contract documents.

2. LOCATION: Bldg. 3-1141, Fort Bragg, NC

3. QUALITY CONTROL: The Contractor shall provide the job superintendent's name and telephone number to the Contracting Officer and to PWBC, Facility Management Division, Butner Road; **Mr. Paul Rodriguez at (910) 432-6609 (3) three days** prior to commencing work.

3.1. The Contractor shall accomplish all work skillfully and in accordance with good industry practices and IAW manufacturer's recommendations and specifications. All work shall conform to current codes and industry and construction standards.

4. SPECIAL PROVISIONS:

4.1. **Hours of Work:** The Contractor shall accomplish all work between the hours of 7:30 a.m. and 4:00 p.m., Monday through Friday. No work will be done on weekends or Federal holidays without prior written approval from the Contracting Officer.

4.2. **EXCAVATION PERMIT:** The Contractor shall have a completed and approved PWBC Excavation Permit in his possession prior to any excavation, to include sign or post-hole holes. The Contractor shall schedule an appointment to locate utility lines at least 24 hours prior to any excavation with the PWBC, Facility Maintenance Division, building 3-1634, Butner Road; (910) 396- 2772. The Contractor shall also be responsible for coordination with the Directorate of Information Management (DOIM), Outside Plant Branch; building 1-1434, Scott Street; (910) 396-8200, for location of communication lines prior to any excavation.

4.3. **OCCUPANCY:** The building will be occupied during accomplishment of work. Interference with and inconvenience to the occupants or routine use of the facility shall be held to an absolute minimum. The Contractor is responsible for providing such coverings, shields, and barricades as required to protect the facility occupants, furniture, equipment, supplies, etc., from dust, debris, weather intrusion, or other damage resulting from construction.

4.4. **CLEAN UP:** The Contractor shall remove all trash, debris or surplus materials from the work site at the end of each work day and shall leave the work site clean of all debris when work is completed. The Contractor shall coordinate with the COR in obtaining a PWBC dumping permit.

4.5. The Contractor shall not employ any person who is an employee of the U.S. Government if the employment of that person would create a conflict of interest.

4.6. Contractor's employees shall wear distinctive clothing bearing the company's name or wear a badge, which contains the company's name and the employee's name, clearly displayed at all times while working on Fort Bragg. The Contractor shall be responsible for the conduct and appearance of his/hers employees while working at Fort Bragg.

4.7. The Contractor is required to adhere to the safety requirements outlined in the Corps of Eng Manual EM 385-1-1.

4.8. Security, Safety, and Fire Protection: While working on Fort Bragg and other Government installations, you are required to comply with all Ft Bragg Security, Fire and Safety regulations/rules. You are also required to comply with all OSHA requirements. Safety equipment must be worn on all construction sites.

4.9. **A minimum of one-year warranty on all materials and workmanship is required.**

5. Vehicle Registration: The Contractor shall fully comply with the vehicle registration requirements regarding contractor-owned and contractor employee privately owned vehicles (POVs) as set forth in Fort Bragg Regulation 190-5. This regulation can be found at http://www.bragg.army.mil/16MP/vehicle_registration_information.htm. Any questions regarding this regulation can be directed to 910-432-8193. Please be advised that Contractor vehicles and contractor employee POVs will be searched if the appropriate passes/decals are not displayed when entering Fort Bragg Access Control Points (ACPs). All vehicles, including those with passes/decals, are subject to random search at any time.

6. Scope of Work: The contractor shall furnish all labor, materials, equipment, transportation, tools, supervision and any other items necessary to: Install a 90-amp, 3-phase circuit and a 1-inch water line to building 3-1141.

6.1. Install 2-sections of 3-inch X ¼-inch thick angle iron on end wall of building 3-1141. Angle iron shall be primed and painted with 2 coats of Federal color #20059 paint. Install a 100-amp, Main Lug, NEMA 3R, 3-phase, 5/wire, 6-circuit, 277/480 volt panel on angle iron. Install EMT across ceiling from 277/480-volt panel at building 3-1240 to corner column. Install EMT down column to ground. Install PVC, 24-inches deep from column to building 3-1141. Install EMT from ground up to 100-amp panel. Install a 90-amp, 3-phase, 5/wire circuit to 100-amp panel.

Install a 90-amp, 3-phase breaker in panel at building 3-1240. Install a 70-amp, 3-phase breaker in 100-amp panel. Install liquid tight conduit from 100-amp panel to drum washer. Install 3-phase, 70-amp circuit to drum washer and make connections.

6.2. Make a 1-inch water tap at water line feeding eye-wash inside of building 3-1141. Install 1-inch copper line across ceiling above mezzanine. Install a braze cut-off valve. Install 1-inch copper from valve to corner column. Install copper down column to first floor. Cut hole in side wall to exterior. Connect 1-inch, 160 psi rated plastic water line to copper line. Install the 1-inch plastic line, 24-inches deep to building 3-1141. Install a 4" X 4" treated post beside end wall. Post shall be installed 3-ft. deep and extend above ground 3-ft. Install a yard hydrant on post. Bottom of hydrant shall be buried 2-ft. deep and top shall extend above ground 3-ft. Casing shall be 1" galvanized steel pipe. Hydrant shall have automatic drain feature to prevent freezing.

6.3. All pipe inside of building shall be wrapped with black foam insulation. Insulation shall be same thickness as existing. Pipe that leaves the building to a depth of 2-ft. shall be wrapped with a minimum of 3-inches thick insulation and covered with a white color weather-proof coating.

(End of Summary of Changes)