

EXCEPTION TO SF 30	30-105-04	STANDARD FORM 30 (Rev. 10-8-80)
APPROVED BY OIRM 11-84		Prescribed by GSA
		FAR (48 CFR) 53.243

## SECTION SF 30 BLOCK 14 CONTINUATION PAGE

**SUMMARY OF CHANGES**

## SECTION 00010 - SOLICITATION CONTRACT FORM

The Issued By organization has changed from  
INSTALLATION BUSINESS OFFICE CONTRACTING  
DRAWER 70120  
FORT BRAGG NC 28307-0120  
to  
INSTALLATION BUSINESS OFFICE CONTRACTING  
ATTN AFZA-IBO-C  
BUILDING 1-1333 ARMISTEAD & MACOMB ST  
FORT BRAGG NC 28310

(End of Summary of Changes)

**The following items are applicable to this modification:**TEXT

- a. The purpose of this amendment is to respond to contractor questions.
- b. The bid opening date remains unchanged at 20 September 2002, 1:00 P.M., Eastern Time.
- c. Contractor questions and the Government responses are indicated below. The questions are as submitted by contractors and have not been edited by the Government.

1. CONTRACTOR QUESTION: What type of Wiring will be required to the Exhaust Fans and GFI Receptacle? I saw some of both when looking in the attic.

- a. Romex 12-2 w/ground
- b. BX Cable 12-2 w/ground

RESPONSE: Either type of wiring conforming to NEC would be acceptable.

2. Item 2 in the Scope of Work Section indicates a 6" diameter vertical discharge grill as a Broan #684. This is an incorrect description for this part number has a square dimension and not round. A vertical discharge exhaust fans has a Broan Part #673 but the specifications is not the same as listed in item-2 of your scope of work. Therefore, which Broan Part Number do you want quoted. The Broan #684 (Square-Vertical) or the Broan #673(Round-Vertical)?

RESPONSE: Scope of Work, Paragraph 2 is revised to read:  
Exhaust fans to be 120V, 80 CFM, 2.5 sones or greater, white grill, Broan #684 or equal.

3. We are requesting that the estimated time of completion be extended from 60 calendar day to 180 calendar days. We estimate that we will lose at least 30 days due to cancellations and unforeseen circumstances that will most likely occur.

RESPONSE: Standard Form 1442, paragraph 11, is revised to read:  
The Contractor shall begin performance within 5 calendar days and complete it within 120 calendar days after receiving Notice to Proceed.

4. Will the metal exhaust pipe be insulated?

RESPONSE: The Metal Pipe will not be insulated.

5. What is the materials on the walls and ceiling of the housing units? The inspector suggested it was sheetrock by another contractor looked inside the ceiling and said it was cement plaster. This would affect the price due to different tool required to cut this material and the length of time to complete this project.

RESPONSE: The materials are 3/8" Plaster on 3/8" Plaster Board.